

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE	PAGE 1	OF PAGES
2. AMENDMENT/MODIFICATION NO. 0005	3. EFFECTIVE DATE 15 July 2002	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. (If applicable)			
6. ISSUED BY U.S. Army Engineer District, Norfolk 803 Front Street Norfolk, VA 23510-1096	CODE DACA65	7. ADMINISTERED BY (If other than Item 6)		CODE		
8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code)				(✓)	9A. AMENDMENT OF SOLICITATION NO. DACA65-02-R-0012	
				X	9B. DATED (SEE ITEM 11) 17 Apr 2002	
				10A. MODIFICATION OF CONTRACTS/ORDER NO.		
				10B. DATED (SEE ITEM 13)		
CODE	FACILITY CODE					
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS						
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers <input type="checkbox"/> is extended, <input checked="" type="checkbox"/> is not extended.						
Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.						
12. ACCOUNTING AND APPROPRIATION DATA (If required)						
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.						
(✓)	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.					
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).					
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:					
	D. OTHER (Specify type of modification and authority)					
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.						
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible) AMENDMENT NO. 0005 to DACA65-02-R-0012, Aerial Delivery and Field Service Training Facility, Fort Lee, VA. Technical specifications are amended. Make appropriate changes in accordance with the attached.						
15A. NAME AND TITLE OF SIGNER (Type or print)				16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)		
15B. CONTRACTOR/OFFEROR		15C. DATE SIGNED		16B. UNITED STATES OF AMERICA		16C. DATE SIGNED
_____ (Signature of person authorized to sign)		BY _____		_____ (Signature of Contracting Officer)		

AMENDMENT 5

July 11, 2002

The Documents are amended as follows:

Drawings:

Drawing C403 - B-6, **Add** the following note: "Monumental sign, locate on south side of building, at entrance driveway, in center of the median, see sheet A601 for elevation and details."
C-3, **Change** note, "3' High x 12' Long Guard Rail", to "**3'-6"** High x 12' Long Guard Rail"
F-4, **Change** note, "2- 12'x 20' Buildings", to "2- 12'x 20' Buildings **N.I.C.** Provide 6" deep gravel pad."
F-4, **Add** a leader to the 10' x 15' dumpster pad with enclosure and the following note: "Perimeter Screen Wall, 6'-0" high, enclose dumpster pad on North, South, and West sides, see similar wall section 7/A306 for details."

Drawing C404 - F-4, **Change** note, "2- 12'x 20' Buildings", to "2- 12'x 20' Buildings **N.I.C.** Provide 6" deep gravel pad."

Drawing C405 - F-4, **Change** note, "2- 12'x 20' Buildings", to "2- 12'x 20' Buildings **N.I.C.** Provide 6" deep gravel pad."

Drawing C406 - F-4, **Change** note, "2- 12'x 20' Buildings", to "2- 12'x 20' Buildings **N.I.C.** Provide 6" deep gravel pad."

Drawing C407 - F-4, **Change** note, "2- 12'x 20' Buildings", to "2- 12'x 20' Buildings **N.I.C.** Provide 6" deep gravel pad."

Drawing A306 - H-4, Typ. Wall Section 7/A101/A306, **Change** note, "8" CMU w/ #5 @ 1'-0" ", to "**Reinforcing: #5 Bars @ 1'-0" O.C.** "

Drawing A308 - D-1-5, Typ. Wall Section 12/A104/A308, **Change** note, "Precast Connection", to "Precast Connection, **See Similar Detail 5/A506, Typ.**" **Delete** note, "Precast slotted insert and wall anchor typ." everywhere it occurs this detail. **Delete** note, "Steel L see Struct. Drawings Typ." and **Add** the following note: "Cont. shelf angle support, See Similar Detail 5/A506, Typ." everywhere it occurs this detail.
F-1-6, Typ. Wall Section 13/A104/A308, **Change** note, "Precast slotted insert and wall anchor typ." to "Cont. shelf angle support, See Similar Detail 5/A506, Typ." everywhere it occurs this detail. **Delete** note, "Steel L see Struct. Drawings Typ." everywhere it occurs this detail. **Delete** note, "Precast bearing connection".

Drawing A330 - D-5, Enlarged Plan @ Loading Dock 1/A105/A330, **Change** note, "Guard Rail, Typ.", to "Guard Rail, **See Similar Detail 5/A507, Typ.**"


Drawing A507 - D-6, Exterior Stair Section Detail 5/A507, **Add** a leader to the 4 dashed lines that project out of the base of the Guard Rail and into the concrete cap with the following note: "2 - #3 x 1'-4" Anchors welded to ea. side of 1-3/4" Pipe Sleeve (Galvanized) w/ 4"x4"x1/4" plate(Galvanized) as base. Extend Pipe Sleeve 6"into concrete cap."

Drawing S101 - A-2, **Add** the following note: "For Entrance Canopy foundation and framing between column line 1 & 4 see Architectural Drawing Sheet A614."
D-6, Footing Schedule, **Add**, "F21 7'-0" x 12'-0" x 1'-0" with 9-#5(S) & #6 @ 3"(L) T&B."
G-3, **Delete** overlay of text below column line 'N' and **Add** text as follows: "Bottom of Col. Ftg. (F) shall be elev. 91.5 unless otherwise shown [xx.x]"
"Bottom of Wall Ftg. (WF) shall be elev. 92.0 unless otherwise shown [xx.x]"

AERIAL DELIVERY AND FIELD SERVICES TRAINING FACILITY _ PHASE I

Drawing A432 - B-5, Add detail, “ Hoist Assembly Detail”, see below.

Hoist Assembly Detail:



Specification Section

Section 07416, - Add to end of paragraph 1.5, Sd-02, “Include snow guards in shop drawing submittal.”

Add paragraph 2.3.1, “Snow Guards. Provide approximately 1,860 individual type snow guards. Locate groups of snow guards on roof above all exterior doors. Snow guards shall be as recommended by the standing seam metal roof manufacturer. Snow guard color to match metal roof. Snow guards to be adhered to flat pan areas of metal roof with adhesive.”

Add paragraph 3.5.1, “Snow Guard Spacing. Horizontal spacing shall be approximately 15” o.c. Space snow guards vertically in two groups of 3 rows each, one group above the other. Space the first/lowest row of snow guards 15” inside the edge of roof. Space rows 15” apart. Stager the location of the guards on each row. Place the second group same as the first group but located 6’-0” up roof from the top of the first group.

Section 10800A, - paragraph 3.3, Schedule, Delete “SNV” everywhere it occurs. **Change** “PTD” to “TTD” everywhere it occurs.

AERIAL DELIVERY AND FIELD SERVICES TRAINING FACILITY _ PHASE I

Section 10990, -paragraph 2.6, **Add** to end of the paragraph “Television mounts shall be located near television cable outlets in rooms 104, 105, 106, 242, 261, and 266.”

Section 14630A, -paragraph 2.3.5, starting on the 3rd line **Delete** “to take the full run of cable for the required lift without overlapping, plus a minimum of 2 full wraps of cable when load is on floor. At least one groove shall remain unused when hook is at the highest position.”

-paragraph 2.1.1, **Change** “crane” to “hoist”.

-paragraph 2.3.7, **Delete** all references to “conical”.

-paragraph 2.3.9, **Change** “Crane” to “System”.

-paragraph 2.4.1.1, **Change** “two speed” to “one speed”.

-paragraph 2.4.2.1, **Delete** the last sentence.

-paragraph 2.4.3.1, **Add** “brake” after “Electric” in the 4th sentence. **Delete** the last 2 sentences.

-paragraph 2.4.4, **Delete** the first 3 sentences.

-paragraph 2.4.4.2.a, **Delete** the last sentence.

-paragraph 3.3, **Change** “where indicated on the drawings” to “in the controller in a protective sleeve”.